

15-095-00254-00-00

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
OCT 25 1973
10:25-73
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drlg Co
Complete Address 705 4th Natl Bldg Wichita, KS
Lease Name Higgins K Well No. 1
Location SE/NW/NW Sec. 15 Twp. 30s Rge. 8 (E) (W)
County Kingman Total Depth 4284
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Russ Casing Pulling Co Inc
Address Box 1182 Great Bend, KS License No. 623
Operation Completed: Hour 2:00 PM Day 23 Month 10 Year 1973

The above well was plugged as follows:

240 ft 8 5/8 surface cemented with 225 sacks. 4280 ft 5 1/2 long string
cemented with 150 sacks. Top perf. 4146 ft. Sand to 4000 ft, 5
sacks cement with bailer. Pulled 3450 ft 5 1/2. Set 10 ft rock bridge
at 320 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/25/73
INV. NO. 8065-02

Signed: [Signature]
Well Plugging Supervisor