

6-050143

10-4

0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-167-21,298
NW SW NE /4 SEC. 36, 15 S, 15 W
3630 feet from S section line
2310 feet from E section line

Operator license# 30893 Lease Becker well # 1

Operator: Prairie Resources Inc. County Russell

Address: P. O. Box 503 Well total depth 3447 feet
Hays, Kansas 67455 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 371 feet

112.02

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: P. O. Box 31, Russell, Kansas

Company to plug at: Hour: AM Day: 4 Month: October Year: 1994

Plugging proposal received from: Dick Green

Company: Prairie Resources Inc. phone: 913-625-9023

Were: 4 1/2" set at 3446 with 175 sx. PBTD at 3392'. Perfs at 3148' to 3295'. Fluid level at 2000' feet. Perfed well at 1650', 930', 420'. Pump down 4 1/2' casing 50 sx 60/40 poz, 8% gel. Pump down 4 1/2" casing 4 sx of gel. Pump down casing 105 sx 60/40 poz, 8% gel. Pressure up on casing. Pump down 8 5/8" X 4 1/2" annular space 30 sx 60/40 poz, 8% gel. Pressure on backside.

Plugging Proposal Received by: Bruce Basye
Plugging operations attended by agent? All[XXX], Part[], None[]

Completed: Hour: 11:40 AM, Day: 4, Month: October, Year: 1994

Actual plugging report: Cement and gel pumped as described above.
Pressure on the 4 1/2" casing at 400# max, 400# shut in. Pressure on the 8 5/8" X 4 1/2" annulus at 500# max, 400# shut in.

Remarks: Low fluid level in well
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X Elevation: 1896 GL

I did observe the plugging.

Bruce D. Basye
Bruce D. Basye
(agent)

INVOICED

DATE 11-3-94

INV. NO. 41572

DEC 12 1994

Form CP-2/3 OCT 07 1994

10-7-94



GAMMA-GUARD SIDE WALL NEUTRON LOG

36-15-15

COMPANY HALLIBURTON OIL
 PRODUCING COMPANY
 WELL BECKER #1
 FIELD RUSSELL
 County RUSSELL
 State KANSAS

COMPANY HALLIBURTON OIL PRODUCING COMPANY

WELL BECKER #1

FIELD APL #15-167-21298

COUNTY RUSSELL STATE KANSAS

Location NW - SW - SE
 Sec 36 Twp 15S Rge 15W

Other Services
 NONE

Permanent Datum GROUND LEVEL Elev. 1896' Elev. K.B. 1904'
 Log Measured From KELLY BUSHING 8 Ft Above Perm Datum D.F. 1270'
 Drilling Measured From KELLY BUSHING G.L. 1270'

Date	5-7-79	5-7-79	5-7-79
Run No	ONE	GAMMA	NEUTRON
Depth - Driller	3445'	3445'	3445'
Depth - Welex	3447'	3447'	3447'
Btm. Log Inter	3419'	3446'	3433'
Top Log Inter	0	2800'	370'
Casing - Driller	8-5/8" @ 371'	@	@
Casing - Welex	8-5/8" @ 370'		
Bit Size	7-7/8"		
Type Fluid in Hole	STARCH		
Dens 1 Visc	9.8 lb		
pH 1 Fluid Loss	6.4 ml		
Source of Sample	FLOW LT		
R _m @ Meas Temp	.152 @	F @	F
R _m @ Meas Temp	.11 @	F @	F
R _m @ Meas Temp	.198 @	F @	F
Source R _m R _m	MEASURE		
R _m @ BHT	.12 @	F @	F
Time Since Circ	3 HOURS		
Rec Temp	104 °F @	F @	F @
Location	702 IG	END	
By	R. R. S		
By	W. W. H		

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 14 1998
 CONSERVATION

4
 10
 11
 12