

6 060497

API NUMBER 15-15-009-21275-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW, SEC. 16, T. 16 S, R. 11 (W/8)

1650 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5217

Lease Name Lumber Well # 1

Operator: S & K Oil Co.

County Barton 110.01

Name & Address Box 559,

Well Total Depth 3385' feet

Tulsa, Ok.

Conductor Pipe: Size _____ feet

74101

Surface Casing: Size 8 5/8" feet 609'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelas Casing Pulling License Number 6050

Address Box 176, Chase, Ok. 69524

Company to plug at: Hour: 2:00 PM Day: 13 Month: March Year: 19 85

Plugging proposal received from Mike Gomez

(company name) Kelas Casing (phone) 316-938-2457

were: Order 165 sh ⁵⁰/₅₀ posmix - 6 sh. Gel - 3 sh. Gel. U., 15 sh. Gel., 5 sh. pulls @ 8 5/8"

plug

STATE CORPORATION COMMISSION

MAR 25 1985
3-25-85
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Guthe E. Lohel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:45 PM Day: 13 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 8 5/8" - 609' cnc. 5 1/2" - 3354' w/ 125 sh. Top perf at 2860'

Plugged bottom w/ 5 sh cement, sand + 5 sh. cement to 2800'. Shot pipe 1 time & recovered 2542'. Pumped in 8 5/8" - 4 sh. pulls, 25 sh. cement, 12 sh. Gel, 4 sh. cement, 3 sh. Gel, 1 sh. pulls, released plug & followed w/ 100 sh. cement w/ 1200 pounds pressure.

Remarks: By Allied
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 3-26-85

Signed Guthe E. Lohel
(TECHNICIAN)

INV. NO. 7456

3-22-85
21