

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-40082-00-00
Spot: SWSWNWNE Sec/Twnshp/Rge: 27-33S-11E
4284 feet from S Section Line, 2381 feet from E Section Line
Lease Name: GREGG Well #: 5
County: CHAUTAUQUA Total Vertical Depth: 1270 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.625	990		0 SX
SURF	10	20		0 SX

Well Type: EOR UIC Docket No: BE0123.1 Date/Time to Plug: 06/16/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: Phone: (620) 725-3636

Proposed Plugging Method: Surface cement and production casing cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' plug of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 06/17/2016 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1050' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 700' and 350'. Ran 1" back into 700' and spotted 25 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 142 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1150	1200		


RECEIVED
KCC DIST # 3
AUG 18 2016
CHANUTE, KS
DS

Remarks: WELL WAS PLUGGED BECAUSE IT WOULD NOT PASS MIT

Plugged through: TBG

District: 03

Signed



(TECHNICIAN) 710

KCC WICHITA

AUG 22 2016

RECEIVED

AUG 31 2016

CC UIC