

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-26830-00-00
Spot: SWSWNWNW Sec/Twnshp/Rge: 8-33S-15E
4115 feet from S Section Line, 5165 feet from E Section Line
Lease Name: SWEARINGEN Well #: 13
County: MONTGOMERY Total Vertical Depth: 1263 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1417		0 SX
SURF	10	20		0 SX

Well Type: EOR UIC Docket No: E23198.3 Date/Time to Plug: 07/13/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull up and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/14/2016 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Tubing and packer was left in well. Could not get them out of hole. Was able to get 180' of tubing out of hole. Drilled and washed down 2" tubing with 1" to 700'. Circulated cement from 700' inside 2" to 180'. Also circulated cement from 180' to surface inside 4". Pulled 1" and topped well off. A total of 32 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1162	1172		

RECEIVED
KCC DIST # 3
AUG 18 2016
CHANUTE, KS
DS

Remarks: WELL PLUGGED DUE TO FAILED MIT.

Plugged through: TBG

District: 03

Signed

[Signature]

(TECHNICIAN)

AUG 31 2016

CC UIC

KCC WICHITA

AUG 22 2016

RECEIVED