

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-21373-00-00
Spot: NENENE Sec/Twnshp/Rge: 21-31S-1E
5003 feet from S Section Line, 568 feet from E Section Line
Lease Name: SOUTHWESTERN COLLEGE Well #: 1
County: SUMNER Total Vertical Depth: 4061 feet

Operator License No.: 33069
Op Name: ENCORE OPERATING COMPANY
Address: PO BOX 27710
DENVER, CO 80227

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4020		350 SX
SURF	8.625	253		120 SX

Well Type: SWD UIC Docket No: D21161.0 Date/Time to Plug: 07/07/2016 10:00 AM
Plug Co. License No.: 34879 Plug Co. Name: CANAAN WELL SERVICE INC.
Proposal Rcvd. from: JAY JOHNSON Company: ENCORE OPERATING CO. Phone: (303) 595-9251

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 07/08/2016 12:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

RIH AND OPERATOR STATES THEY CAN NOT GET PAST 3,000'. DISTRICT 2 SUPERVISOR APPROVED OPERATOR TO PLUG WELL FROM THERE. RIH WITH TUBING TO 3075' AND SPOT 35 SX OF COMMON CEMENT WIT 3% CC. PULLED UP 10 JOINTS. WAITED AN HOUR TAGGED CEMENT @ 2947', CSG STOOD FULL. PERFORATED @ 300' CIRCULATED 90 SX OF COMMON W/ 3% CC TO SURFACE. CAME BACK AND CUT OFF CASING BELOW GROUND.

Perfs:

Top	Bot	Thru	Comments
3494	3496	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed

Daniel B. Fox
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

AUG 25 2016

CONSERVATION DIVISION
WICHITA, KS

AUG 31 2016

Form CP-2/3

cc uic

JK