

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-32461-00-00
Spot: SWNENENW Sec/Twnshp/Rge: 7-34S-14E
4722 feet from S Section Line, 3183 feet from E Section Line
Lease Name: BURRIS Well #: 9
County: MONTGOMERY Total Vertical Depth: 1462 feet

Operator License No.: 35005
Op Name: BPG CAPITAL, LLC
Address: 2532 OLD HIGHWAY 166
CANEY, KS 67333

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	21		10 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/18/2016 12:00 AM
Plug Co. License No.: 31696 Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: RON CUNNINGHAM Company: _____ Phone: (620) 330-2724

Proposed Plugging Method: Run 2" to bottom, gel hole, spot 12 sacks cement on bottom, pull up to 850', spot 12 sacks of cement, pull up to 500', spot 12 sacks of cement, pull up to 225', cement to surface, pull tubing out, top off cement.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 05/18/2016 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report: Ran 2" to 1452' gelled hole and spotted 12 sack plug. Pulled up to 850' and spotted 12 sack plug. Pulled up to 500' and spotted 12 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 2" and topped well off. A total of 118 sack of cement were used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
AUG 16 2016
CHANUTE, KS

DS

Remarks:
Plugged through: TBG

District: 03 Signed Don A Sims
(TECHNICIAN)

KCC WICHITA
AUG 22 2016
RECEIVED

NO
AUG 31 2016 Form CP-2/3