

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19451-00-00
Spot: SWNESE Sec/Twnshp/Rge: 23-31S-5E
1650 feet from S Section Line, 990 feet from E Section Line
Lease Name: SU-CA RISING Well #: 4
County: COWLEY Total Vertical Depth: 2341 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2339		75 SX
SURF	8.625	200		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2016 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: _____ Phone: (316) 524-1225

Proposed Plugging Method: According to the rules and regulations of the KCC.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/01/2016 8:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @2215', DUMP BAILED 2 SXS CEMENT ON TOP OF CIBP. RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 250' - 251'(4-HOLES). RIH W/TBG@260', GRESSEL ESTABLISHED CIRCULATION, MIXED AND PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 8/2/2016. GRESSEL CEMENT TICKET #44804.

Perfs:

Top	Bot	Thru	Comments
2310	2320		LAYTON A

Remarks: COMPLIANCE/10 YR

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

NO
AUG 31 2016 Form CP-2/3