

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-21173-00-00
Spot: S2NESE Sec/Twnshp/Rge: 20-18S-31W
1650 feet from S Section Line, 660 feet from E Section Line
Lease Name: INMAN TRUST Well #: 1-20
County: SCOTT Total Vertical Depth: 4710 feet

Operator License No.: 35345
Op Name: BREHM ASSET MANAGEMENT, LLC
Address: 11625 CUSTER RD SUITE 110-363
FRISCO, TX 75035

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	348		WITH 250 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/27/2016 3:30 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TIM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 2250' WITH 50 SX CMT. 2ND PLUG AT 1470' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 390' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 07/27/2016 5:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 2250' WITH 50 SX CMT. 2ND PLUG AT 1470' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 390' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY GLOBAL CEMENTING.

Plugged through: DP

District: 01

Signed [Signature]

(TECHNICIAN)

RECEIVED
AUG 18 2016
KCC DODGE CITY

70
AUG 31 2016

Form CP-2/3

KMS