

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01789-00-01

Spot: NENENE

Sec/Twnshp/Rge: 34-23S-11E

330 feet from N Section Line,

330 feet from E Section Line

Lease Name: SOUTH

Well #: 1

County: GREENWOOD

Total Vertical Depth: 1980 feet

Operator License No.: 5193

Op Name: BARNARD, R.L. DBA BARNARD OIL O

Address: 907 S 3RD PO BOX 535

MADISON, KS 66860

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1964		50 SX
SURF	8	113		0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/02/2016 1:00 PM

Plug Co. License No.: 7719

Plug Co. Name: CHEEVER WELL SERVICE, INC.

Proposal Rcvd. from: DICK BARNARD

Company:

Phone: (620) 437-2131

Proposed
Plugging
Method:

As per KCC regulations and recommendations. In 1986 this well had a new 3" liner ran to 1946' and was cemented to the surface with 134 sacks of cement with 5% gel.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/02/2016 4:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran 1" hydrill to 1921' pumped 10 sxs cement, pulled pipe to 1000' pumped 10 sxs cement, pulled pipe to 250' pumped 10 sxs cement to surface, gel spacers between cement plugs.

RECEIVED
KCC DIST #3
AUG 22 2016
CHANUTE, KS

MH

Remarks:

Plugged through: TBG

District: 03

Signed

Mike Heffern

(TECHNICIAN)

KCC WICHITA

AUG 29 2016

RECEIVED

NO
AUG 31 2016

Form CP-2/3