

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23602-00-01
Spot: SWSWSE Sec/Twnshp/Rge: 36-20S-24W
331 feet from S Section Line, 2251 feet from E Section Line
Lease Name: MCCREIGHT Well #: 1-36
County: NESS Total Vertical Depth: 4369 feet

Operator License No.: <u>30104</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>CAMBRON, PAUL L.</u>	PC		1476		WITH 210 SX CMT
Address: <u>118 N PENN PO BOX 384</u>	PROD	5.5	4364	0	WITH 100 SX CMT
<u>NESS CITY, KS 67560</u>	SURF	8.625	212		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/18/2016 10:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: HAL HOSS Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-2282

Proposed Plugging Method: RUN TBG TO 4200' & PUMP 135 SX CMT. PULL TBG TO 1500' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. PRESSURE BACKSIDE WITH CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/18/2016 2:45 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PORT COLLAR @ 1476' WITH 210 SX CMT. CASING LEAK AT 3550'. RAN TBG TO 4200' & PUMPED 135 SX CMT WITH 200# HULLS. PULLED TBG TO 1500' & LET CMT FOR AWHILE. MIKE MAIER WITNESSED THE REST OF THE PLUG JOB. BACKSIDE WAS PRESSURED TO 300# WITH 10 SX CMT. PUMP 145 SX CMT AT 1500'. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 10 SX CMT.	Perfs:			
	Top	Bot	Thru	Comments
	4278	4285		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
AUG 19 2016
KCC DODGE CITY [Signature]

No
AUG 31 2016

Form CP-2/3

KMS