

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-22738-00-00
Spot: E2NENE Sec/Twnslp/Rge: 30-18S-25W
4507 feet from S Section Line, 271 feet from E Section Line
Lease Name: TENNY A Well #: 2
County: NESS Total Vertical Depth: 4427 feet

Operator License No.: 4656
Op Name: DAVIS PETROLEUM, INC.
Address: 7 SW 26 AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	4.5	1722		WITH 350 SX CMT
PROD	4.5	4425	0	WITH 200 SX CMT
SURF	8.625	340		WITH 210 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/12/2016 9:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: MIKE KASSELMAN Company: DAVIS PETROLEUM Phone: (620) 793-3051

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 150# HULLS. PULL TBG TO 1730' & CIRCULATE TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2016 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4410' WITH 35 SX CMT & 150# HULLS. PULL TBG TO 1732' & PUMPED 150 SX CMT & 400# HULLS. DID NOT CIRCULATE. PULLED TBG TO 1039' & PUMPED 12 SX GEL & 200# HULLS. GOT CIRCULATION. PUMP 130 SX CMT & 200# HULLS. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 40 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4419	4423		
4220	4222		
4187	4189		
4183	4187		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

Signed Michael Maier

(TECHNICIAN)

RECEIVED
AUG 17 2016
KCC DODGE CITY

NO
AUG 31 2016

Form CP-2/3

KMS