

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-22431-00-00
Spot: SWNE Sec/Twnshp/Rge: 3-20S-9W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: MARKLE 20-9 Well #: 1-3
County: RICE Total Vertical Depth: 3450 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2060		
CIBP	5.5	3008		
PROD	5.5	3425		180 SX
SURF	8.625	234		
SURF	8.625	282		235 SX
T1	2.375	2139		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/18/2016 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS. CEMENT BOND LOG RAN IN 2004 SHOWING CEMENT ON BACKSIDE AT 1150', GETTING OUT OF CEMENT AT 1050'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 07/18/2016 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL OUT 1900' OF TUBING & TAG CIBP @ 2060'. PERFORATE AT 750' AND 332'. RUN TUBING TO 2055' AND PUMP 35 SX'S CEMENT. PULL TUBING UP AND WAIT 2 HRS. LOWER TUBING BACK DOWN AND TAG CEMENT AT 1843'. PULL TUBING TO 1150' AND PUMP 20 SX'S CEMENT. PULL TUBING TO 750' AND PUMP 35 SX'S, PULL TUBING TO 332' AND CIRCULATE TO SURFACE. PULL TUBING OUT AND TOP OFF. USED COMMON CEMENT ON JOB.

Perfs:

Top	Bot	Thru	Comments
3227	3230	CSG	
3196	3200	CSG	
3070	3090	CSG	
3008		CSG	
2948	2954	CSG	
2326	2432	CSG	
2134	2146	CSG	
2116	2124	CSG	
1973	1983	CSG	

Remarks: LOG TECH OF KS. #8747. COPELAND TICKET #C-44163.

Plugged through: TBG

District: 02

Received
KANSAS CORPORATION COMMISSION Signed

Virgil Clothier *TD*
(TECHNICIAN) **AUG 31 2016**

AUG 25 2016

CONSERVATION DIVISION
WICHITA, KS

JK