

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22910-00-00
Spot: N2NWSWNE Sec/Twnshp/Rge: 21-31S-11W
1370 feet from N Section Line, 2310 feet from E Section Line
Lease Name: THREE SISTERS Well #: 1
County: BARBER Total Vertical Depth: 5035 feet

Operator License No.: 35162
Op Name: DIXON OPERATING COMPANY, LLC
Address: 8100 E. 22ND ST N BLDG 300, SUITE 20
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3730		WITH 2 SX CMT
CIBP		4380		
CIBP		4600		
PROD	5.5	4780	2228	WITH 200 SX CMT
SURF	8.625	275		WITH 275 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/12/2016 8:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: TIMOTHY DIXON Company: DIXON OPERATING Phone: (316) 264-9632

Proposed Plugging Method: CIBP @ 3736' WITH 2 SX CMT. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 08/12/2016 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

CIBP @ 3730' WITH 2 SX CMT. 1ST PLUG AT 730' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 292' WITH 50 SX CMT. 3RD PLUG AT 63' WITH 25 SX CMT. FELL BACK 100+ FEET. TOPPED OFF WITH 1 1/2 YDS READY MIX.

Top	Bot	Thru	Comments
4625	4635		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: CSG

District: 01

RECEIVED
AUG 17 2016
KCC DODGE CITY

Signed _____

(TECHNICIAN) NO

AUG 31 2016

Form CP-2/3

KMS