

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-02265-00-00  
Spot: NWSWSWSE Sec/Twnshp/Rge: 1-34S-15E  
468 feet from S Section Line, 2348 feet from E Section Line  
Lease Name: BURROWS Well #: 3  
County: MONTGOMERY Total Vertical Depth: 870 feet

Operator License No.: 7582  
Op Name: DELOZIER, ORVAL & STEVENS, FLOY  
Address: PO BOX 64  
DEWEY, OK 74029

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	8.5	780		
PROD	5.5	0		0 SX
SURF	10	0		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/27/2016 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: JOHN ELMORE Company: \_\_\_\_\_ Phone: (620) 249-2519

Proposed Plugging Method: Run through 1 inch in well to bottom. 1 to 2 sacks of gel put in bottom plug in to surface. pull up and put middle plug in close to T.D. Bottom plug and cement to casing.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE  
Date/Time Plugging Completed: 06/14/2016 12:00 AM KCC Agent: DUANE SIMS

**Actual Plugging Report:**

**Perfs:**

Ran 1" down through 2" to 780' gelled hole and spotted 20 sack plug. Pulled 1" out. Hooked onto 2" and worked it free. Pulled 2" and fishing tool out. Perforated casing at 400' and 225'. Ran 1" to 400' and spotted 20 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 125 sacks of cement were used to plug this well.

RECEIVED  
KCC DIST # 3  
AUG 16 2016  
CHANUTE, KS

DS

Remarks:

Plugged through: TBG

District: 03

Signed *Dual*

(TECHNICIAN)

KCC WICHITA

AUG 22 2016

RECEIVED

*No*  
AUG 31 2016