

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-40342-00-00  
Spot: NENENE Sec/Twnshp/Rge: 8-26S-5E  
330 feet from N Section Line, 330 feet from E Section Line  
Lease Name: SIGMAN Well #: 3  
County: BUTLER Total Vertical Depth: 2426 feet

Operator License No.: 35293

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2419		48 SX
SURF	8.625	45		40 SX

Op Name: D & L OIL, LLC

Address: 10066 SE PAWNEE RD  
LEON, KS 67074

Well Type: OIL

UIC Docket No:

Date/Time to Plug:

Plug Co. License No.: 31538

Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL

Proposal Revd. from: DENNIS BUTLER

Company:

Phone: (316) 323-4654

Proposed Method: Tally tubing going in , have consolidated set 35 sacks of common on top of junk. Run in with wire line and confirm at least 100' of cement above bottom formation. Pull tubing out of hole and have Cornish shoot holes at 250' below surface. Then run tubing back down to 250', and have Consolidated run cement from 250' to surface. Cut surface pipe to 3' below surface and clean area up

Plugging Proposal Received By: DUANE KRUEGER

Witness Type: PARTIAL

Date/Time Plugging Completed: 08/16/2016 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/ TBG @ 2029', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC, 1/2# HULLS & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 1672'. RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 250'-251' (4 HOLES). RIH W/TBG @ 250', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 140 SXS CLASS A COMMON, LOST CIRCULATION. TAGGED CEMENT PLUG @ 1157'. RIH W/TBG @ 250', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 180 SXS CLASS A COMMON 3% CC TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #51334. 8-12-2016, TAGGED CEMENT PLUG @ 200'. 8-16-2016, TOPPED WELL BACK TO SURFACE W/ CNC DUMPED 35 SXS CLASS A COMMON TO SURFACE. (1-3/4 YDS). PLUGGING COMPLETE 8-16-2016 5:00 PM

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)

MD  
AUG 31 2016

Form CP-2/3