

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-22912-00-00
Spot: SESESENE Sec/Twnshp/Rge: 31-33S-8E
2948 feet from S Section Line, 328 feet from E Section Line
Lease Name: SNYDER B Well #: 5
County: COWLEY Total Vertical Depth: 2237 feet

Operator License No.: 32679
Op Name: AAS OIL CO., INC.
Address: 2508 EDGEMONT DR STE # 4
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2236		85 SX
SURF	8.625	163		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2016 12:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: GARY ANSTINE Company: _____ Phone: (620) 441-8165

Proposed Plugging Method: set CIBP @ 2140 bale 3 sacks cement on plug. set CIBP @ 1830 bale 3 sacks cement on plug. perf casing @ 500' circulate cement to surface

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/21/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2140', DUMP BAILED 3 SXS CEMENT ON TOP OF PLUG. RIH ON WIRELINE SET CIBP @ 1830", DUMP BAILED 3 SXS CEMENT ON TOP OF PLUG. RIH W/TBG @ 510', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 180 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
2166	2172		
1856	1866		

Remarks: CEMENT TICKET # 51310, COMPLIANCE 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

NO
AUG 31 2016

Form CP-2/3

1/2