

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-22207-00-00  
Spot: NESWSWNW Sec/Twnshp/Rge: 20-33S-8E  
2994 feet from S Section Line, 4831 feet from E Section Line  
Lease Name: N MILLS Well #: 1  
County: COWLEY Total Vertical Depth: 2485 feet

Operator License No.: 32679  
Op Name: AAS OIL CO., INC.  
Address: 2508 EDGEMONT DR STE # 4  
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2485		100 SX
SURF	8.625	130		60 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/21/2016 12:00 AM  
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.  
Proposal Rcvd. from: GARY ANSTINE Company: \_\_\_\_\_ Phone: (620) 441-8165

Proposed Plugging Method: set CIBP @ 2390. bale 4 sacks cement on plug. perf squeeze holes @ 500feet circulate cement to surface.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/21/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2388', DUMP BAILED 4 SXS CEMENT ON TOP OF PLUG. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @ 500'-501'. RIH W/TBG @ 500', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 205 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
2420	2427		

Remarks: CEMENT TICKET #51309 COMPLIANCE/10 YR RULE

Plugged through: TBG

District: 02

Signed Duane Krueger ND  
(TECHNICIAN)

AUG 31 2016

JK