

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-22854-00-00  
Spot: SWSWSEW Sec/Twnshp/Rge: 19-33S-8E  
2655 feet from S Section Line, 9802 feet from E Section Line  
Lease Name: RICE Well #: 4  
County: COWLEY Total Vertical Depth: 2632 feet

Operator License No.: 32679  
Op Name: AAS OIL CO., INC.  
Address: 2508 EDGEMONT DR STE # 4  
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2632		125 SX
SURF	8.625	170		75 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/20/2016 12:00 AM  
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.  
Proposal Rcvd. from: GARY ANSTINE Company: \_\_\_\_\_ Phone: (620) 441-8165

Proposed Plugging Method: set cast iron bridge plug @ 2460 bale 4 sacks cement on plug. perf squeeze holes @ 500 feet circulate cement to surface

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/21/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2640', DUMP BAILED 4 SXS CEMENT ON TOP OF PLUG. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @500'-501'. RIH W/TBG @ 510', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 158 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
2584	2590		
2480	2494		

Remarks: CEMENT TICKET #51311 COMPLIANCE/ 10 YR RULE

Plugged through: TBG

District: 02 Signed Duane Krueger (TECHNICIAN)

NO  
AUG 31 2016

✓