

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-21716-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 4-19S-28W  
329 feet from S Section Line, 3566 feet from E Section Line  
Lease Name: SCHMIDT Well #: 3  
County: LANE Total Vertical Depth: 4400 feet

Operator License No.: 30269  
Op Name: ARGENT ENERGY, INC.  
Address: 1313 N WEBB RD STE 210  
WICHITA, KS 67206

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| DVT    | 4.5   | 2122       |             | WITH 385 SX CMT |
| PROD   | 4.5   | 4400       | 0           | WITH 125 SX CMT |
| SURF   | 8.625 | 265        |             | WITH 160 SX CMT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/19/2016 8:30 AM  
Plug Co. License No.: 35052 Plug Co. Name: HUSKER ENERGY SERVICES, INC.  
Proposal Rcvd. from: BRAD SEIB Company: HUSKER ENERGY SERVICES, INC. Phone: (785) 798-2184

Proposed Plugging Method: RUN TBG TO DV TOOL & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/19/2016 10:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

\*\*THE DV TOOL WAS NEVER DRILLED OUT & THERE ARE NO PERFS IN THE CASING.\*\* RUN TBG TO 2111' & PUMPED 145 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & COULDN'T PUMP INTO.

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier

(TECHNICIAN)

RECEIVED  
AUG 23 2016  
KCC DODGE CITY AP

No  
AUG 31 2016

Form CP-2/3

KMS