

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20975-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 3-33S-19W
4309 feet from S Section Line, 4939 feet from E Section Line
Lease Name: WEBSTER Well #: 3-4
County: COMANCHE Total Vertical Depth: 5405 feet

Operator License No.: 33770
Op Name: ARES ENERGY, LTD
Address: 405 N. MARIENFELD SUITE 250
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4890		WITH 2 SX CMT
COND	20	138		
PROD	5.5	5405	2403	WITH 210 SX CMT
SURF	8.625	653		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/03/2016 8:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4890' WITH 2 SX CMT. PLUG AT 950' WITH 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/03/2016 12:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 4890' WITH 2 SX CMT. 1ST PLUG AT 941' WITH 15 SX GEL & 60 SX CMT. 2ND PLUG AT 704' WITH 60 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT. TOP OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5199	5202		
5190	5196		
5177	5183		
5019	5024		
5004	5006		
4993	5202		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED
AUG - 5 2016
KCC DODGE CITY

Signed [Signature] ECRS
(TECHNICIAN) 700
SA

AUG 31 2016