

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-23385-00-00
Spot: NWENWSW Sec/Twnshp/Rge: 34-34S-3E
2337 feet from S Section Line, 4506 feet from E Section Line
Lease Name: REYNOLDS Well #: 1
County: COWLEY Total Vertical Depth: 3460 feet

Operator License No.: 32887
Op Name: ENDEAVOR ENERGY RESOURCES, LP
Address: 110 N MARIENFELD, STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2153		135 SXS CMT
SURF	8.625	304		200 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/20/2016 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GUS MYERS Company: _____ Phone: (918) 244-8063

Proposed Plugging Method: Set CIBP @ 1900' and spot 4 sks cement; shoot 3 squeeze holes @315' ; Run 325' 2.375 tbg and circulate cement to surface

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 07/28/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 1900', DUMP BAILED 4 SXS CEMENT ON TOP OF PLUG. PERFORATED SQUEEZE HOLES 315'-316'. RIH W/ TBG @ 325', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 170 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING, TOPPED WELL BACK TO SURFACE W/10 SXS.

Perfs:

Top	Bot	Thru	Comments
2052	2056		

Remarks: CEMENT TICKET # 650000257. COMPLIANCE

Plugged through: TBG

District: 02

Signed Jeff Klock, District Supervisor
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

AUG 25 2016

CONSERVATION DIVISION
WICHITA, KS

AUG 31 2016

Form CP-2/3