

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-071-20741-00-00
Spot: NE Sec/Twnshp/Rge: 29-20S-40W
3957 feet from S Section Line, 1317 feet from E Section Line
Lease Name: HOUSEHOLDER Well #: 2-29
County: GREELEY Total Vertical Depth: 2850 feet

Operator License No.: 4894
Op Name: HORSESHOE OPERATING, INC.
Address: 110 W LOUISIANA STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2847	0	WITH 445 SX CMT
SURF	8.625	308		WITH 190 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/26/2016 11:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: TOOH WITH RODS & TBG. PUMP DOWN 4 1/2" CASING WITH 150# HULLS & 180 SX CMT TO 2798'. PRESSURE TO 500#. ATTEMPT TO PUMP CMT DOWN ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/26/2016 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2798' TO 0' USING 150# HULLS & 190 SX CMT. PRESSURED TO 400#. HOLDING. PUMP 5 SX CMT DOWN THE ANNULUS TO 300#. HOLDING.

Perfs:


Top	Bot	Thru	Comments
2794	2798		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
AUG - 4 2016
KCC DODGE CITY

Form CP-2/3

AUG 18 2016

