

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-071-20707-01-00
Spot: S2S2N2NW Sec/Twnshp/Rge: 12-20S-40W
1250 feet from N Section Line, 1320 feet from W Section Line
Lease Name: WATSON E Well #: 2-H
County: GREELEY Total Vertical Depth: 2836 feet

Operator License No.: 4894
Op Name: HORSESHOE OPERATING, INC.
Address: 110 W LOUISIANA STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2600		
LI	2.375	2880		2685-2880
PROD	5.5	2719	0	WITH 360 SX CMT
SURF	8.625	309		WITH 185 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/01/2016 5:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: BRETT COOK Company: HORSESHOE OPERATING Phone: (620) 847-8267

Proposed Plugging Method: CIBP @ 2600' WITH 2 SX CMT. FILL CASING WITH CMT FROM 2300' TO 0'. ATTEMPT TO PUMP CMT DOWN ANNULUS

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/02/2016 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2600'. SPOT CMT FROM 2600' TO 1200' WITH 120 SX CMT. SPACER TO 320'. PUMP 30 SX CMT FROM 320' TO 0'. PRESSURE TO 500#. HOLDING. PUMP 15 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
2719	3271	OH	

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED. TMD = 3271'

Plugged through: CSG

District: 01

Signed *Ken Jehlik*
SA (TECHNICIAN)

RECEIVED
AUG - 4 2016
KCC DODGE CITY