

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-071-20778-00-00
Spot: NWSEW Sec/Twnshp/Rge: 12-20S-40W
1650 feet from N Section Line, 1650 feet from W Section Line
Lease Name: WATSON E Well #: 3-12
County: GREELEY Total Vertical Depth: 2853 feet

Operator License No.: 4894
Op Name: HORSESHOE OPERATING, INC.
Address: 110 W LOUISIANA STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2876	0	WITH 650 SX CMT
SURF	8.625	298		WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/02/2016 1:30 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: BRETT COOK Company: HORSESHOE OPERATING Phone: (620) 847-8267

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING WITH 200# HULLS & 185 SX CMT TO 2834'. PRESSURE TO 500#. ATTEMPT TO PUMP CMT DOWN ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/02/2016 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2834' TO 0' USING 210 SX CMT & 150# HULLS. PRESSURE TO 500#. HOLDING. PUMP 2 SX CMT DOWN THE ANNULUS & PRESSURE TO 250#.

Perfs:

Top	Bot	Thru	Comments
2828	2834		SPF - 13 SHOTS TO

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
5A

(TECHNICIAN)

RECEIVED
AUG - 4 2016
KCC DODGE CITY

Form CP-2/3

AUG 18 2016
no