

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-21589-00-00
Spot: W2NESW Sec/Twnshp/Rge: 24-31S-22W
1980 feet from S Section Line, 1650 feet from W Section Line
Lease Name: GILES RANCH Well #: 24-1
County: CLARK Total Vertical Depth: 6400 feet

Operator License No.: 4247
Op Name: DOLOMITE RESOURCES CORPORATIO
Address: 2250 N ROCK RD. NO. 118-1
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	734		WITH 400 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/24/2016 9:45 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY STRUTT Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 6320' WITH 50 SX CMT. 2ND PLUG AT 1110' WITH 50 SX CMT. 3RD PLUG AT 780' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 07/24/2016 11:45 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 6320' WITH 50 SX CMT. 2ND PLUG AT 1110' WITH 50 SX CMT. 3RD PLUG AT 780' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY BASIC SERVICES.

Plugged through: DP

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
JUL 25 2016
KCC DODGE CITY

Form CP-2/3

AUG 18 2016