

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-05279-00-00
Spot: SESESW Sec/Twnshp/Rge: 8-12S-17W
314 feet from S Section Line, 3070 feet from E Section Line
Lease Name: SCHMEIDLER B Well #: 1
County: ELLIS Total Vertical Depth: 3667 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: 114 NORTH MAIN P.O. BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3654		125 SX
SURF	8.75	176		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2016 2:00 PM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: DAVE HEIN Company: GRADY BOLDING CORPORATION Phone: (785) 623-2804

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 3398' - 3408', 3418' - 3426', 3444' - 3448', 3450' - 3458', 3462' - 3472', 3532' - 3540'.
Squeezed at 1215' w/150 sx cement, 1200' w/50 sx cement, 824' w/350 sx cement, 1224' w/80 sx cement, 900' w/115 sx cement and 2833' w/150 sx cement.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2016 5:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Professional Pulling Service removed retrievable plug at 3306'. Perf Tech perforated at 1850' and 1373'. Professional Pulling Service ran in hole with tubing to 3300'. Quality rigged to tubing and pumped 150 sx cement w/300 # hulls mixed in. Pulled tubing to 1850'. Rigged to tubing and pumped 150 sx cement w/200 # hulls to circulate cement to surface. Pulled tubing. Rigged to 5 1/2" casing and pumped 50 sx cement to pressure with 300 psi. Shut in pressure 300 psi. Rigged to 8 5/8" surface casing and pumped 15 sx cement. Blew a hole in the top of the head.

GPS: 39.01714 -099.23376

Perfs:

Top	Bot	Thru	Comments
3532	3540	---	
3462	3472	---	
3450	3458	---	
3444	3448	---	
3418	3426	---	
3398	3408	---	

Remarks: QUALITY CEMENTING CO. TICKET # 1990

Plugged through: TBG

District: 04

Signed _____

KCC WICHITA

AUG 18 2016

RECEIVED


(TECHNICIAN)

CM

JUL 27 2016

Form CP-2/3

8/18/16
20