

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-20766-00-01
Spot: NESW Sec/Twnshp/Rge: 33-8S-18W
1980 feet from S Section Line, 3300 feet from E Section Line
Lease Name: MOSHER Well #: 1-WD
County: ROOKS Total Vertical Depth: 3495 feet

Operator License No.: 32278 String Size Depth (ft) Pulled (ft) Comments
Op Name: TENGASCO, INC. PROD 4.5 3485 200 SX
Address: 1327 NOOSE RD PO BOX 458 SURF 8.625 260 135 SX
HAYS, KS 67601

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/18/2016 12:00 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Production perforations: 3109' - 3394'.
Perforated at 1390' and squeezed with 550 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/18/2016 2:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Knocked CIBP from 2810' - 3150'. Ran tubing to 3120' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 2000' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1100' and pumped 75 sx cement to circulate cement to surface. Pulled all tubing. Hooked to 4 1/2" casing and pumped 5 sx cement. Shut in pressure 300 psi. Hooked to 8 5/8" x 4 1/2" annulus and pumped 1/2 bbl. Shut in pressure 300 psi.

GPS: 39.31239N -099.33757W

Perfs:

Top	Bot	Thru	Comments
3371	3377		
3348	3356		
3330	3338		
3177	3394		
3159	3162		
3109	3112		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1987

Plugged through: TBG

District: 04

Signed

Pat Bedore

KCC WICHITA

(TECHNICIAN)

CM

JUL 17 2016

AUG 18 2016

RECEIVED

Form CP-2/3

8/18/16
no