

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26364-00-00
Spot: NWSENWSW Sec/Twnshp/Rge: 33-14S-18W
1725 feet from S Section Line, 900 feet from W Section Line
Lease Name: LEGLEITER-STECKLEIN UNIT Well #: 1
County: ELLIS Total Vertical Depth: 3750 feet

Operator License No.: 32875 String Size Depth (ft) Pulled (ft) Comments
Op Name: CWB OIL COMPANY, LLC PROD 5.5 3747 150 SX
Address: P.O. BOX 742 SURF 8.625 220 150 SX
ST. FRANCIS, KS 67756

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/03/2016 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 20 sx gel.
PBTD: 3720'
DV Tool at 1188' w/125 sx cement.
Low fluid levels.
Perforations: 3453' - 3456', 3514' - 3516', 3550' - 3553', 3666' - 3669'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/03/2016 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality pulled rods and tubing, rigged to 5 1/2" casing with a swedge and pumped 50 sx cement w/200 # hulls mixed in, followed by 20 sx gel, followed by 170 sx cement w/300 # hulls mixed in pressured to 900 psi. Shut in pressure 500 psi. Rigged to 8 5/8" casing and pumped 15 sx cement w/900 psi. Shut in pressure 200 psi.

GPS: 38.78886 -099.33428

Perfs:


Top	Bot	Thru	Comments
3514	3516		
3453	3456		
3366	3369		
3350	3353		

Remarks: QUALITY WELL SERVICE INC. TICKET # 6125

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

AUG 18 2016

RECEIVED

AUG 08 2016

Form CP-2/3

8/18/16
920