

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-05964-00-01
Spot: SESENE Sec/Twnshp/Rge: 33-14S-13W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: CARTER A Well #: 3
County: RUSSELL Total Vertical Depth: 2931 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2831		150 SX
SURF	10.75	623		450 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/01/2016 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROESTSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-5371

Proposed Plugging Method: Ordered 550 sx 60/40 pozmix 4% gel cement, 10 sx gel and 400 # hulls.
Casing collapsed at 2117'.
Tubing was parted leaving 2 joints of 2 3/8" tubing in the well.
PBSD at 2820'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/01/2016 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1350' and 600'. Ran tubing to 2100' and pumped 10 sx gel followed by 75 sx clean cement, followed by 75 sx cement w/200 # hulls. Both backside and braden head started to circulate. Pulled tubing to 1152' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 600' and pumped 180 sx cement. Cement circulated out the backside. Shut in the backside and pumped 100 sx cement. Braden head circulated good cement. POOH. Hooked to 7" casing and pumped 20 sx cement. Braden head shut in. Pressured casing to 150 psi. Shut in. Pulled off swedge after an hour and casing was full.

GPS: 38.79208 -098.76334

Perfs:


Top	Bot	Thru	Comments
2831	2931		
2794	2802		
2772	2777		
2703	2707		
2520	2526		
2199	2210		

Remarks: HURRICAN SERVICE TICKET # 100651

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

AUG 18 2016

RECEIVED

AUG 08 2016

Form CP-2/3

8/18/16
700