

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21990-00-00
Spot: NENESENW Sec/Twnshp/Rge: 17-11S-26W
1477 feet from N Section Line, 2519 feet from W Section Line
Lease Name: Q-B Well #: 1-17
County: GOVE Total Vertical Depth: 4632 feet

Operator License No.: 34579
Op Name: COBALT ENERGY LLC
Address: 115 S. BELMONT #12 PO BOX 8037
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4620		175 SX
SURF	8.625	260		185 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/02/2016 12:00 PM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: DIRK PARKS Company: COBALT ENERGY LLC DBA Phone: (785) 216-0039

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 14 sx gel.
Port Collar at 2230' w/200 sx cement.
Perforations: 4049' - 4054'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/02/2016 3:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4042' and pumped 14 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 2300' and pumped 100 sx cement. Pulled tubing to 1400' and pumped 110 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 25 sx cement. Tied on to backside and squeezed with 15 sx cement. Shut in pressure 200 psi.

GPS: 39.09958 -100.23215

Perfs:


Top	Bot	Thru	Comments
4496	4500		
4049	4054		

Remarks: SWIFT CEMENT TICKET # 29584

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

KCC WICHITA

AUG 18 2016

RECEIVED

AUG 08 2016

Form CP-2/3

8/18/16
MD