

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-23444-00-00
Spot: SWSNWSE Sec/Twnshp/Rge: 36-13S-20W
1640 feet from S Section Line, 1775 feet from E Section Line
Lease Name: ERNEST PFEIFER Well #: D-1
County: ELLIS Total Vertical Depth: 3949 feet

Operator License No.: 34741
Op Name: GREYSTONE, INC.
Address: PO BOX 506
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3949		225 SX
SURF	8.625	248		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/10/2016 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JASON CLARK Company: GREYSTONE INC. Phone: (785) 259-5575

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 3855' - 3859'
DV Tool-Yes, with 100 sx cement

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2016 11:40 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service ran in hole to 3700'. Swift rigged to tubing and pumped 110 sx cement w/300 # hulls mixed in. Pulled tubing to 2050'. Swift rigged to tubing and pumped 140 sx cement w/200 # hulls to circulate cement to surface. Pulled tubing. Rigged to 4 1/2" casing and pumped 20 sx cement. Hole standing full. Pulled valve off of 8 5/8" surface casing and hole is still full of cement.

GPS: 38.87529 -099.49079

Perfs:

Top	Bot	Thru	Comments
3855	3859		

Remarks: SWIFT CEMENTING SERVICES TICKET # 29436

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

AUG 15 2016

KCC WICHITA

AUG 18 2016

RECEIVED

Form CP-2/3

8/18/16
no