

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-21255-00-00  
Spot: SEWNNE Sec/Twnshp/Rge: 3-15S-19W  
4290 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: DECHANT Well #: 1  
County: ELLIS Total Vertical Depth: 3799 feet

Operator License No.: 33864 String Size Depth (ft) Pulled (ft) Comments  
Op Name: HABIT PETROLEUM, LLC PROD 4.5 3799 125 SX  
Address: 639 280TH AVE PO BOX 243 SURF 8.625 230 125 SX  
HAYS, KS 67601

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/09/2016 8:30 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: J R HASELHORST Company: HABIT PETROLEUM Phone: (785) 623-1154

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls.  
CIBP set at 3370'.  
DV Tool set at 1315'

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/09/2016 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 3350' and pumped 150 sx cement. Backside started to circulate. Pulled tubing to 1400' and pumped 110 sx cement. Cement circulated to pit. POOH. Hooked to braden head and pumped 25 sx cement with 200 psi. Shut in. Topped off with 15 sx cement. Casing standing full.

GPS: 38.78105 -099.41731

Remarks: GLOBAL CEMENTING TICKET # 2675

Plugged through: TBG

District: 04

Signed

RAY DINKEL

(TECHNICIAN)

CM

AUG 15 2016

KCC WICHITA

AUG 18 2016

RECEIVED

Form CP-2/3

8/18/16  
20