

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23577-00-00
Spot: S2NENW Sec/Twnshp/Rge: 16-7S-24W
990 feet from N Section Line, 1980 feet from W Section Line
Lease Name: BESSIE MAY Well #: 1
County: GRAHAM Total Vertical Depth: 4050 feet

Operator License No.: 33593
Op Name: BARRACUDA OPERATING COMPANY
Address: PO BOX 405
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4050		150 SX
SURF	8.625	305		240 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/01/2016 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: BRIAN GABEL Company: BARRACUDA OPERATING COMPA Phone: (785) 798-3122

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls and 13 sx gel.
DV Tool at 2171' w/420 sx cement.
Perforations: 3871' - 3872'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/01/2016 5:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3931' and pumped 13 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 2250' and pumped 100 sx cement. Pulled tubing to 1350' and pumped 135 sx cement. Pulled tubing out and topped of casing with 15 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 300 psi.

GPS: 39.44823 -100.00569

Perfs:


Top	Bot	Thru	Comments
3871	3872		

Remarks: ALLIED CEMENT TICKET # 68063

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)


CM

KCC WICHITA

AUG 18 2016

RECEIVED

Form CP-2/3



AUG 18 2016