

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-23578-00-00  
Spot: SWSWSESW Sec/Twnshp/Rge: 16-7S-24W  
178 feet from S Section Line, 1332 feet from W Section Line  
Lease Name: BESSIE MAY Well #: 2  
County: GRAHAM Total Vertical Depth: 4000 feet

Operator License No.: 33593  
Op Name: BARRACUDA OPERATING COMPANY  
Address: PO BOX 405  
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3998		125 SX
SURF	8.625	263		180 SX
T1	2.875	3936		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/01/2016 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: BRIAN GABEL Company: BARRACUDA OPERATING COMPA Phone: (785) 798-3122

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls and 13 sx gel.  
DV Tool at 2087' w/125 sx cement.  
Perforations: 3874' - 3876', 3909' - 3912'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/01/2016 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3917' and pumped 13 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 2158' and pumped 100 sx cement. Pulled tubing to 1221' and pumped 120 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 10 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 400 psi.

GPS: 39.43688 -100.00800

Perfs:

Top	Bot	Thru	Comments
3909	3912		
3874	3876		

Remarks: ALLIED CEMENT TICKET # 68062

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

  
(TECHNICIAN)

(M)

AUG 08 2016

KCC WICHITA

AUG 18 2016

RECEIVED

Form CP-2/3

