

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-193-20964-00-00
Spot: NENWNWSW Sec/Twnshp/Rge: 12-6S-33W
2620 feet from S Section Line, 540 feet from W Section Line
Lease Name: LEIKER UNIT Well #: 1
County: THOMAS Total Vertical Depth: 4610 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 263 | | 175 sx |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/25/2016 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 255sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 07/25/2016 11:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st plug @2725 w/50 sx
2nd plug @1900 w/100 sx
3rd plug @300 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: QUALITY

Plugged through: DP

District: 04

Signed _____



KCC WICHITA

(TECHNICIAN)

JUL 29 2016

AUG 18 2016

RECEIVED

Form CP-2/3

8/18/16
200