

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-20124-00-00
Spot: NESESW Sec/Twnshp/Rge: 18-15S-12W
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: PARKER EST Well #: 1
County: RUSSELL Total Vertical Depth: 3300 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: 9415 E. HARRY STREET, SUITE 403 BU
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3309		125 SX
SURF	8.625	248		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2016 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DON BROWNING Company: YOUNGER ENERGY Phone: (785) 810-8230

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 14 sx gel and 600 # hulls.
Perforations: 1300'
Holes in casing from 390' - 580'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/21/2016 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3272' and pumped 14 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1367' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 604' and pumped 70 sx cement. Had good cement returns. POOH. Hooked up to braden head and pumped 30 sx cement. Topped off casing with 10 sx cement. Casing stayed full.

GPS: 38.74322 -098.69934

Perfs:

Top	Bot	Thru	Comments
3304	3311		
3294	3297		
3200	3207		
3104	3109		
3052	3058		

Remarks: QUALITY CEMENTING TICKET # 1735

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

KCC WICHITA

(TECHNICIAN)

cm

AUG 18 2016

RECEIVED

Form CP-2/3
8/18/16
920