

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22954-00-00
Spot: NWNENW Sec/Twnshp/Rge: 34-26S-6E
4962 feet from S Section Line, 3587 feet from E Section Line
Lease Name: CARR Well #: 1
County: BUTLER Total Vertical Depth: 2787 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2780		75 SX
SURF	8.625	208		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2016 8:00 AM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Rcvd. from: DWAIN STOUT Company: R.R.A. INC. Phone: (316) 262-3411

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 06/20/2016 1:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2735'. RIH W/ TBG @ 2720', COPELAND ACID MIXED & PUMPED 25 SXS CLASS A COMMON & DISPLACED IN CASING. LAYED DOWN 21 JTS TBG, W/TBG @ 2100', COPELAND ACID MIXED & PUMPED 20 SX GEL PLEG TO SURFACE. TAGGED CEMENT @ 650'. RIH ON WIRELINE @ 260', PERFORATED 2 HOLES (260'-261'). RIH W/TBG @ 270', COPELAND ACID SERVICE, ESTABLISHED CIRCULATION, MIXED & PUMPED 55 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TUBING, SWEDGED INTO 4.5" CASING MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P&A COMPLETE 6-20-2016 1:30 PM. 6-22-2016, TOPPED WELL BACK TO SURFACE W/7 SXS.

Perfs:

Top	Bot	Thru	Comments
2780	2787	Oil	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

Form CP-2/3

AUG 18 2016
JK