

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40201-00-00
Spot: NESWNE Sec/Twnshp/Rge: 29-26S-7E
3614 feet from S Section Line, 1699 feet from E Section Line
Lease Name: GUENTHER A Well #: 5
County: BUTLER Total Vertical Depth: 2772 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION DBA A
Address: PO BOX 1020
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2736		20 SX
SURF	6.62	2752		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/17/2016 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: BRADY SHARP Company: AZTEC OIL CO. Phone: (316) 321-3800

Proposed
Plugging
Method:

AS PER KCC RULES & REGS / SAND @ 2680, W/5 SXS OIRC. 250'-0".

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/20/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/SANDPUMP ON WIRELINE, TAGGED TD @ 2,765'. SANDED WELL BACK @ 2690' (1,000# SAND) DUMP BAILED 5 SXS CEMENT ON TOP OF SAND. TAGGED CEMENT PLUG @ 2665'. SDON. 6-20-2016, RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 250'-251'. RIH W/TBG @ 250', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 300 SXS 60/40 POZMIX 4% GEL 1.5% CC W/HULLS TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 6-20-2016. CONSOLIDATED CEMENT TICKET #51272.

Top	Bot	Thru	Comments
2736	2772	OH	

Remarks: 10 YR COMPLIANCE

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

AUG 18 2016
mo