

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-21083-00-00  
Spot: SEWNNE Sec/Twnshp/Rge: 29-26S-7E  
4248 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: GUENTHER B Well #: 4  
County: BUTLER Total Vertical Depth: 2810 feet

Operator License No.: 5387  
Op Name: THE BUCKEYE CORPORATION DBA A  
Address: PO BOX 1020  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2801		
PROD	5.5	2809		150 SX
SURF	8.62	203		85 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/15/2016 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: BRADY SHARP Company: AZTEC OIL CO. Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND @ 2680, W/ 5 SXS CIRC. 250'-Ø.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/16/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/SANDPUMP ON WIRELINE, TAGGED TD @ 2,770', SANDED WELL BACK @ 2630' (1,600# SAND). 6/16/2016 DUMP BAILED 5 SXS CEMENT ON TOP OF SAND. TAGGED CEMENT PLUG @ 2605'. RIH ON WIRELINE CUT CASING @ 247', LAYED DOWN 5.5" CASING (7 JOINTS). RIH ON WIRELINE BAILED WELL @ 250', CMC DUMPED 6 YARDS (120 SXS) SLURRY MIX TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 6-16-2016. CMC CEMENT TICKET #400044438.

Perfs:

Top	Bot	Thru	Comments
2741	2743	CSG	
2736	2739	CSG	

Remarks: 10 YR COMPLIANCE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)

Form CP-2/3

AUG 18 2016  
JK