

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19488-00-00
Spot: NESESE Sec/Twshp/Rge: 20-26S-7E
987 feet from S Section Line, 333 feet from E Section Line
Lease Name: JOHNSON Well #: 3
County: BUTLER Total Vertical Depth: 2189 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION DBA A
Address: PO BOX 1020
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	8.25	217		
PROD	8.25	2176		45 SX
SURF	0	0		0 SX
SURF	8.625	2176		45 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/21/2016 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: BRADY SHARP Company: AZTEC OIL CO. Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND @ 2125, 2/8 SXS CIRC. 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/22/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/SANDPUMP ON WIRELINE, TAGGED BRIDGE @ 30', RIH W/TBG CIRCULATING VARIOUS BRIDGES @ 2176', 6-22-2016, WITH TUBING @ 2176', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 30 SXS CLASS A COMMON 2% CC & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 2110'. RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 250', (4 HOLES). RIH W/ TBG @ 250', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 220 SXS 60/40 POZMIX 4% GEL 4% CC 1/2 # POLY FLAKE TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 6-22-2016. CONSOLIDATED CEMENT TICKET #51303.

Perfs:

Top	Bot	Thru	Comments
2176	2189	CSG	

Remarks: 10 YEAR COMPLIANCE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

Form CP-2/3
AUG 18 2016

JK

JK