

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19564-00-00
Spot: NENESWNW Sec/Twnshp/Rge: 14-24S-12E
3723 feet from S Section Line, 1076 feet from W Section Line
Lease Name: SULLIVAN Well #: 15
County: GREENWOOD Total Vertical Depth: 1784 feet

Operator License No.: 33861
Op Name: ALLEN'S SERVICE INC. DBA RUDE CR
Address: PO BOX 145
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1730		
PROD	7	1740		0 SX
SURF	16	4		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/27/2016 8:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: ALLEN DANNELS Company: _____ Phone: (620) 678-3836

Proposed Plugging Method: Bridge plug in bottom with 20 sacks cement. Perforated at 700 feet with 2 holes cement with 20 sacks. Cement 150 feet to surface on inside and outside of pipe. Set jell bridges between cement.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/27/2016 12:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

bridge set @ 1700' 20 sxs cement, casing shot @ 700' 20 sxs cement, pulled casing to 150' ran 1" down backside of casing toto 150' pumped 78 sxs cement inside of 7" casing to surface, 48 sxs cement on backside to surfac, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1740	1784		

RECEIVED
KCC DIST # 3
AUG 01 2016
CHANUTE, KS

MH

Remarks:
Plugged through: TBG

District: 03

Signed Mike Heffern (TECHNICIAN)

KCC WICHITA
AUG 08 2016
RECEIVED

Form CP-2/3
AUG 18 2016

MH