

6-8  
4-071001

42  
R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-009-24,519-0000

SW NE NW /4 SEC. 07, 16 S, 11 W  
4290 feet from S section line  
3530 feet from E section line

Operator license# 9911 Lease Schremer well # 1

Operator: HAR-KEN Oil Company County Barton 109.68

Address: 2932 NW 122 Well total depth 3375 feet  
Unit 15 Conductor Pipe: 0 inch @ 0 feet  
Oklahoma City, OK 73120 Surface pipe 8 5/8 Inch @ 380 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: L.D. Drilling License# 6039

Address: Great Bend, Kansas 67530

Company to plug at: Hour: A.M. Day: 8 Month: June Year: 92

Plugging proposal received from: Greg Davidson

Company: L.D. Drilling Phone: 405-752-0318

Were: 8 5/8" 380' S.P. circ. w/170 sx. 60/40 pozmix - 2% gel. - 3% cal.cl. By Halliburton. Arbuckle well. Elev. 1875'. Anhy. 730'. No circulation problems. Mud Condition 50 vis. 9.2 weight - 10 water loss. Proposal 175 sx. 60/40 pozmix - 6% gel. - 1 sx. F.C. Spot with drill stem. Circulate hole heavy mud between all plugs. 25 sx. @ 3240' 25 sx. @ 750' - 100 sx. @ 480' - 10 sx. @ 40' - 15 sx. in Rathole. Circulate.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 5:30P.M., Day: 8, Month: June, Year: 92

Actual plugging report: Ordered 175 sx. 60/40 pozmix - 6% gel. - 1 sx. flocele - circulated hole. Spot with drill stem, heavy mud between all plugs.

1st. plug @ 3280' w/25 sx.  
2nd. plug @ 750' w/25 sx.  
3rd. plug @ 480' w/100 sx. w/1 sx. flocele.  
4th. plug @ 40' w/10 sx.  
15 sx. in Rathole. Circulate.

Remarks: Cemented by Halliburton.

Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: 1875 GL

I did  / did not  observe the plugging.

DATE 8-20-92

INV. NO. 36008

*Marion J. Schmidt*  
(agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 17 1992  
8-17-92  
CONSERVATION DIVISION  
Wichita, Kansas