

4-062587

2-24

75-
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-03019-0000

SW SW /4 SEC. 08, 16 S, 11 W
660 feet from S section line
4620 feet from E section line

Operator license# 6988

Lease Ney A well # 1

Operator: Smith Oil Operation

County Barton 107.12

Address: P.O. Box 550
Hutchinson, Kansas 67504

Well total depth 3296 feet P.B.3231'
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 Inch @ 300 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License# -

Address: P.O. Box 595 - Great Bend, Kansas 67530

Company to plug at: Hour: 1:00P.M. Day: 24 Month: February Year: 92

Plugging proposal received from: Willard French

Company: Smith Oil Company Phone: 316-663-6622

Were: Order 400 sks. 60/40 posmix - 8% gel. - 5 sks. hulls.

Plugging Proposal Received by: Gilbert G. Scheck
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 3:00P.M., Day: 24, Month: February, Year: 92

Actual plugging report: 8" @ 300' w/0 sks. 4 1/2" @ 3292' w/70 sks.
Top perf. @ 3096'. Pump in 2 3/8" tubing and circulated cement to
surface w/400 P.S.I. w/200 sks. cement. 8" no cement w/250 P.S.I.
Max. pressure on 8" - 400 P.S.I. Shut in @ 250 P.S.I.
Max. pressure on backside - 200 P.S.I. Shut in @ 200 P.S.I.
Total sacks 200 cement. 3-9-92

Remarks:

Condition of casing(in hole):GOOD BAD Anhy.plug:YES 710 NO
Bottom plug(in place):YES ,CALC ,NO Dakota plug:YES ,NO
Plugged through TUBING , CASING . Elevation: 1835 GL

I did[] / did not[] observe the plugging.

Gilbert G. Scheck

(agent)

Form CP-2/3

INVOICED

DATE MAR 23 1992

INV. NO. 34808
2-24

HD