

RECEIVED  
STATE CORPORATION COMMISSION

6-3-83  
JUN 03 1983

15-009-23,003-0000

CONSERVATION DIVISION  
Wichita, Kansas  
To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

NE, Sec. 8, T 16 S, R 11 W 1/4

2310 feet from N/E section line

2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6283

Lease Name O'Leary Well # 4

Operator: Romana Corporation  
Name & Address Box 1162, Great Bend, Ks.  
67530

County Boston

Well Total Depth 3271 feet \$106.31

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 326

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering Inc. License Number 5111

Address Box 698, Great Bend, Ks. 67530

Company to plug at: Hour: \_\_\_\_\_ Day: 1 Month: 6 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO D. B. Pulic

(company name) Rockhold Engineering Inc. (phone) 316-792-2506

were: Order 165 lbs. 50 posmix - 4 7/8" 3% col. cl., 5 sh. hulls,  
15 sh. hull. + 8 5/8" plug

Signed Guthrie R. Leibel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:00 PM Day: 1 Month: 6 Year: 1983

ACTUAL PLUGGING REPORT 8 5/8" - 326' SP. WC. w/ 200 sh. 4 1/2" set at 3267'

Top perf. at 3266'. Plugged bottom w/ 4 sh. cement, sand & 4 sh. cement, shot pipe 2 times & recovered 2500'

Pumped in 8 5/8" SP., 4 hulls, 12 sh. gel, 65 cement, 3 sh. gel, 1 sh. hulls, released plug & followed w/ 100 sh. cement w/ 1000 pounds pressure

Remarks: Cemented By Sun Cementing Co. Great Bend, Ks.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Guthrie R. Leibel  
(TECHNICIAN)

INVOICED  
DATE 6-9-83  
INV. NO. 4538-W

FORM CP-2/3  
Rev. 9-82