

To: 1 080051
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-075-20,165-0001

App. NW SE SW, SEC. 9, T 24 S, R 39 W/X
1285 feet from S section line
1503 feet from W X section line

7-17

TECHNICIAN'S PLUGGING REPORT

Operator License / 5952
Operator: Amoco Production Company
Name:
Address P.O. Box 800, Room 924
Denver, CO 80201

Lease Name B. Masterson Well / 1-9
County Hamilton 177.12
Well Total Depth 5450 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 377

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X _____

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling License Number 5382

Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 8:45 p.m. Day: 16 Month: 7 Year: 19 96

Plugging proposal received from Jack Pepper

(company name) Cheyenne Drilling (phone) 316-277-2062

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3100' with 100 sx cement, 2nd plug at 1970' with 50 sx cement,

3rd plug at 800' with 50 sx cement, 4th plug at 390' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X _____

Operations Completed: Hour: 7:45 a.m. Day: 17 Month: 7 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 3100' with 100 sx cement,

2nd plug at 1970' with 50 sx cement, 3rd plug at 800' with 50 sx cement,

4th plug at 390' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 22 1996
CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED
I (did not) observe this plugging.

DATE 7-24-96
INV. NO. 46077

Signed Kevin D Strube (TECHNICIAN)

EFFECTIVE DATE: 6-29-96

State of Kansas

FORM MUST BE TYPED

DISTRICT # 1
SEA? Yes No

NOTICE OF INTENTION TO DRILL 075-20,604

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well.

Spot APPROX.

Expected Spud Date June 25, 1996
month day year

NW - SE - SW Sec 9 Twp 24 S, Rg 39 East West

OPERATOR: License # 5952
Name: Amoco Production Company
Address: PO Box 800 Room 924
City/State/Zip: Denver, CO 80201
Contact Person: Susan R. Potts
Phone: 303-830-5323

1285 feet from South / North line of Section
1503 feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Hamilton
Lease Name: B. Masterson Well #: 1-9
Field Name: Wildcat

CONTRACTOR: License #: 5382
Name: Cheyenne Drilling

* Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Morrow

Nearest lease or unit boundary: 1285'
Ground Surface Elevation: 3290.08 feet MSL

Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 740'
Depth to bottom of usable water: 740'

Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: _____

Length of Conductor pipe required: _____
Projected Total Depth: 5400'

Formation at Total Depth: St. Louis
Water Source for Drilling Operations: _____
... well ... farm pond X other

Well Drilled For: Well Class: Type Equipment:

X Oil ... Enh Rec ... Infield X Mud Rotary
X Gas ... Storage ... Pool Ext. ... Air Rotary
X WWO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes ... Other

Old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth: _____
Bottom Hole Location: _____

Will Cores Be Taken?: yes X no
If yes, proposed zone: _____

Exp. 12/24/96

AFFIDAVIT

* SPACED IN THE CONDUCTOR INFORMATION.
320' ALT. II RECEIVED

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 22 1996
CONSERVATION DIVISION
WICHITA, KS

Pusher <u>Jack Lewis</u>	INIT. <u>aw</u>
SPUD DATE <u>7-9-16</u>	
LENGTH SURFACE PLANNED _____	
RESERVE PIT STATUS- REMOVE FLUID _____ LINED _____	
after salt sect. _____ bbls. when done _____ bbls.	
RATHOLED AHEAD? <u>Y</u> N SIZE HOLE _____	
SURFACE PIPE <u>24</u> @ <u>377'</u> CONDUCTOR _____	
ANHYDRITE T- <u>5450</u> B- <u>7470'</u> ELEVATION _____	
TD <u>5400'</u> FORMATION <u>St. Louis</u>	
RAN PIPE @ _____ DV TOOL _____ ALT II DONE _____	
_____ SX _____ SX Y _____ N _____ SX	
Arbuckle Plug @ _____ Ft. W/ _____ SX	
_____ Plug / Council @ <u>3100'</u> Ft. W/ <u>100'</u> SX ✓	
_____ Anhydrite Base @ <u>1970'</u> Ft. W/ <u>50'</u> SX ✓	
_____ 1/2 Base Anhy. @ <u>800'</u> Ft. W/ <u>50'</u> SX ✓	
_____ 1/2, 1/2 Plug @ _____ Ft. W/ _____ SX	
_____ Bottom Surface @ <u>390'</u> Ft. W/ <u>50'</u> SX ✓	
_____ 40' Plug @ <u>40'</u> Ft. W/ <u>10'</u> SX ✓	
RAT HOLE CIRC/W <u>15</u> SX MOUSE HOLE W/ <u>10</u> SX	
WATER WELL _____ SX (Irr. Well _____ Pond _____)	
TECHNICIAN _____ DATE _____ Hauling _____	
TYPE OF CEMENT <u>60/40 6% gel</u>	
STARTING TIME <u>20:45 (AM/PM)</u> DATE <u>7-16</u>	
COMPLETION TIME <u>07:45</u> (AM/PM) DATE <u>7-17</u>	
CEMENT COMPANY <u>Hall</u>	