

TO: *R*
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-00387-00-00
Spot: C Sec/Twnshp/Rge: 36-24S-38W
2640 feet from N Section Line, 2640 feet from E Section Line
Lease/Unit Name: BAUMGARDNER Well Number: 1
County: KEARNY Total Vertical Depth: 2670 feet

Operator License No.: 5249
Op Name: OSBORN HEIRS COMPANY, LTD
Address: PO BOX 17968
SAN ANTONIO, TX 78217

Conductor Pipe: Size _____ feet:
Surface Casing: Size _____ feet:
Production: Size 7 feet: 2484
Liner: Size _____ feet:

\$86.78

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/06/2001 3:30 PM
Plug Co. License No.: 32297 Plug Co. Name: SUPERIOR SERVICING, INC.
Proposal Rcvd. from: RICHARD GEIER Company: OSBORN HEIRS Phone: (316) 373-2701

Proposed Plugging Method: WITH TBG, SET BALANCED PLUG THROUGH SLOTTED LINER FROM 2614-2430'. ATTEMPT TO RELEASE 4 1/2' CASING ON PACKER. IF SUCCESSFUL, PULL OUT OF HOLE WITH 4 1/2". IF UNSUCCESSFUL, DETERMINE FREE POINT OF 4 1/2". IF FREE BELOW 1200', CUT AT FREE POINT AND PULL OUT OF HOLE WITH 4 1/2" CASING. CIRCULATE HOLE WITH MUD TO 750'. PERFORATE 7" AT 700'. ATTEMPT TO CIRCULATE ANNULUS BEHIND 7" CASING. IF CIRCULATION ESTABLISHED, CMT 7" TO SURFACE. LEAVE 20 SX PLUG INSIDE 7" CASING. TOP OF PLUG INSIDE WILL BE AT 600'. IF CIRCULATION IS NOT ESTABLISHED, SQUEEZE PERFORATIONS WITH 200 SX CMT. FILL SURFACE CASING/7" ANNULUS FROM SURFACE. CIRCULATE HOLE WITH MUD. SET 100' PLUG INSIDE 7".

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/07/2001 9:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2614'. 4 1/2" LINER FROM 0' TO 1970'. 5 1/2" SLOTTED LINER @ 2484' TO 2670'. RAN TUBING IN HOLE TO 2494'. PUMPED 200# HULLS & 60 SX CMT. DISPLACED TO BOTTOM. PULLED TUBING UP TO 1400'. SDON. 08/0701 RAN IN HOLE WITH TUBING. TAGGED CMT AT 2224'. PERFORATED AT 700'. RAN TUBING IN HOLE TO 1525'. LOADED HOLE WITH MUD. PUMPED 50 SX CMT WITH 100# HULLS MIXED IN. PULLED TUBING TO 750' PUMPED 135 SX CMT. CIRCULATED CMT TO SURFACE. PULLED TUBING OUT. PUMPED DOWN 7" 35 SX CMT. CIRCULATE 10 3/4 TO SURFACE. PULLED 4 1/2" LINER TO 1772' GOT STUCK. SHOT OFF AT 1732' LAID DOWN.

RECEIVED
AUG 15 2001
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED. RECOVERED LINER.

Plugged through: TBG

District: 01

Signed *Kevin D. Strube*
(TECHNICIAN)

INVOICED

DATE 8-15-01 AUG 09 2001

INV. NO. 2002060236