

TO: **STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202**

API Well Number: 15-093-00374-00-00
Spot: NWNWNWSE Sec/Twnshp/Rge: 26-24S-38W
2540 feet from S Section Line, 2540 feet from E Section Line
Lease/Unit Name: STUART Well Number: 1
County: KEARNY Total Vertical Depth: 2705 feet

Operator License No.: 5249
Op Name: OSBORN HEIRS COMPANY, LTD
Address: PO BOX 17968
SAN ANTONIO, TX 78217

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 705 WITH 350 SX CMT
Production: Size 5.5 feet: 2684 WITH 375 SX CMT
Liner: Size _____ feet: \$87.91

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/08/2001 11:15 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: RICHARD GEIER Company: OSBORN HEIRS Phone: (316) 373-2701

Proposed Plugging Method: CIBP @ 2490' WITH 3 SX CMT ON TOP. PERFORATE AT 735'. PUMP CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/08/2001 12:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2600'. PERFS AT 2538-2584'. SET CIBP @ 2490' WITH 3 SX CMT ON TOP. PERFORATED AT 735'. PUMPED 46 BBL MUD & 145 SX CMT. CIRCULATED CMT TO SURFACE.

RECEIVED
8-15-2001
AUG 15 2001
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

INVOICED

Plugged through: CSG

DATE 8-15-01
INV. NO. 2002060236

District: 01

Signed Kevin D. Strube
(TECHNICIAN)

AUG 09 2001

Form WP-2/3

MP