

To: ¹ 090623
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION 11-13
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-093-20,627-0000
W/2 SE, SEC. 24, T. 24 S, R. 37 W/EX
1320 feet from S section line
1960 feet from E section line
Lease Name Wheeler Gas Unit B Well # 2
County Kearny 97.79
Well Total Depth 3009 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 620

TECHNICIAN'S PLUGGING REPORT
Operator License # 5952
Operator: Amoco Production Company
Name & Address P.O. Box 800, Room 924
Denver, CO 80201

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____
Plugging Contractor Halliburton License Number _____
Address _____

Company to plug at: Hour: 10:30 a.m. Day: 13 Month: 11 Year: 19 95
Plugging proposal received from Richard Perez
(company name) Amoco Production Company (phone) 316-356-7016
wells: 5 1/2" at 3009' w/700 sx cement, PBTD 3001, Perfs at 2750-2842' (6 sets)
1st plug fill 5 1/2" casing with 2 sx hulls and cement,
Check backside.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11:30 a.m. Day: 13 Month: 11 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 240 sx cement and 2 sx hulls.
Maximum pressure 200 psi and shut in 80 psi.

2nd plug pumped 5 sx cement down backside. Shut in pressure 180 psi.

Remarks: Used 65/35 Pozmix 6% gel by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED (XXXXXX) observe this plugging.

DATE 11-16-95
INV. NO. 44035
11-13

Signed _____
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1995
CONFIRMATION
WICHITA, KANSAS
11-15-95