

1 051276

3-8

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 093-20,335-0000
C NE, SEC. 16, T 24 S, R 38 W/E
3960 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4253
Operator: Plains Petroleum Operating Co.
Name & Address P.O. Box 383
Lakin, KS 67860

Lease Name Jackson Well # 1-2
County Kearny 97.50
Well Total Depth 3000 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 543

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton License Number _____
Address P.O. Box 1598, Liberal, KS 67905-1598

Company to plug at: Hour: 10 a.m. Day: 8 Month: 3 Year: 19 90

Plugging proposal received from Wayne King

(company name) Plains Petroleum Operating Company (phone) 316-355-7838

were: 4 1/2" at 2992' PBTB 2876' Perfs at 2756-2828' TOC on 4 1/2" 840' Elevation 3275' GL
1st plug pump 150 sx cement down 8 5/8" X 4 1/2" annulus.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 8 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 4 1/2" casing with 2 sx hulls and 133 sx cement.
Maximum pressure 800 psi and shut in 200 psi.

2nd plug pumped down 8 5/8" X 4 1/2" annulus with 25 sx cement, Maximum pressure 400 psi,
braden head blew up.

Remarks: Used light cement by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-14-90

INV. NO. 27655

CONSERVATION DIVISION
Wichita, Kansas 3-12-90

Signed Richard W Lacey
(TECHNICIAN)